



# Test and Calibration of Large Drift Tube Chambers

**IEEE NSS 2004 - 19. October 2004**

O. Biebel, T. Christiansen, J. Dubbert, J. Elmsheuser, F. Fiedler,  
R. Hertenberger, O. Kortner, T. Nunnemann, F. Rauscher, D. Schaile,  
A. Staude, R. Ströhmer, C. Vollmer

Contact: [joerg.dubbert@physik.uni-muenchen.de](mailto:joerg.dubbert@physik.uni-muenchen.de)



Ludwig-Maximilians-Universität München



- Introduction
- The LMU Cosmic Ray Facility
- Chamber Commissioning
- Chamber Calibration
- Summary



# Introduction



# Introduction (1)

## ATLAS Muon Spectrometer

- Air Core Toroid Magnet System


- Area:  $> 5500 \text{ m}^2$

- 788 Trigger Chambers

- 1226 Precision Chambers

- 32 Cathode Strip Chambers (CSC)


- 1194 Monitored Drift Tube (MDT) Chambers





# Introduction (2)

## Monitored Drift Tube Chambers



- Drift tubes
  - Aluminum tubes, 3 cm outer diameter, 400  $\mu\text{m}$  wall thickness
  - Centered anode wire, 50  $\mu\text{m}$  diameter
  - Gas mixture:  $\text{Ar}/\text{CO}_2 = 93/7$
  - Pressure: 3 bar
  - Gas gain:  $2 \times 10^4$
  - Max. drift time:  $\approx 700 \text{ ns}$
  - Averaged resolution: 100  $\mu\text{m}$
- 2 multilayer of 3 (or 4) tube layer
- Support frame of aluminum
- Optical (RasNik) systems to monitor chamber deformations
- Chamber size: 1-11  $\text{m}^2$
- Optical chamber to chamber alignment



# Introduction (3)

Physics requirements: -  $\Delta p_T/p_T < 10\%$  up to 1 TeV  
- Stand-alone operation

Sagitta measurement with 3 MDT stations

→ 50  $\mu\text{m}$  point resolution needed

→ 20-30  $\mu\text{m}$  RMS on wire positions needed

**Guaranteed by chamber design and monitoring**

...




# The LMU Cosmic Ray Facility



# Setup (1)

- Chamber size: 3.8 m × 2.2 m  
2 × 3 layers, 72 tubes per layer



- 2 Scintillator hodoscopes
- Full chamber coverage (8.7 m<sup>2</sup>)
- 5 segments along tubes
- < 800 ps time resolution
- 7.5 cm track resolution along tube
- Iron Absorber ( $\Rightarrow E_{\mu} > 600$  MeV)
- Streamer tubes (energy cut based on multiple scattering)
- 2 Reference chambers certified by X-Ray tomograph
- Optical and capacitive alignment monitors (< 5  $\mu$ m precision)
- 80 Hz trigger rate  
15-25 M events / chamber
- Test chamber can be shifted








# Programme

Commission and calibrate 88 BOS/BOF MDT chambers built at the  
Max-Planck-Institut für Physik



- Fix leaks / Measure leak rate
- Complete chamber
- Equip with & test front-end electronics
- HV test
- Commission chamber (tube response, homogeneity)
- Calibrate chamber (wire positions, geometry)

**Goal: MDTs ready for installation and operation in ATLAS**




# Commissioning



# Tube Response


- Measure drift time spectra
- Fit analytic functions at beginning and end
- Parameter set
  - Maximum drift time
  - Rise time
  - Noise level
  - ...





# Chamber Homogeneity

## Maximum Drift Time



Very good agreement between multilayers

N.B.: Error bars denote single tube RMS spread



# Calibration



Physics requirements: . . .

→ 20-30  $\mu\text{m}$  RMS on wire positions needed


**Guaranteed by chamber design and monitoring**

but. . .

- Some geometry parameters difficult to control during production (e.g. layer distances)
- Longterm stability (chamber production started end of 2000)
- Anchor points for calibration / reconstruction at LHC



# Method



$$y = y_0 + m^{-1} \cdot z$$

- Wire positions derived from comparison of predicted drift radius  $r_{\text{ref}}$  (weighted average reference tracks) and measured drift radius  $r_{\text{drift}}$  in the test chamber  


$$\Delta r = r_{\text{drift}} - r_{\text{ref}} \approx \delta_z - m \cdot \delta_y$$
- $\delta_y$  from linear fit of  $\Delta r$  vs.  $m$
- $\delta_z$  from  $\langle \Delta r' \rangle = \delta_z - \langle m \rangle \cdot \delta_y' \approx \delta_z$  ( $\Delta r'$  with corrected  $y$  pos.)
- Grid scaling factor  $\gamma$ :  

$$z(n) = z_0 + \gamma \cdot g_{\text{nom}} \cdot n$$





# Performance



BOS5A08

(Exceptional chamber with known production error)


Comparison of measurements of Cosmic Ray Facility with X-Ray Tomograph gives accuracy

- Perpend. to chamber plane
  - $\delta_y$ :  $25 \mu\text{m}$
  - $\delta_{y, \text{Layer}}$ :  $4.5 \mu\text{m}$
  - $\alpha_{x, \text{Layer}}$ :  $17 \mu\text{rad}$
- In chamber plane
  - $\delta_z$ :  $8 \mu\text{m}$
  - $\delta_{z, \text{Layer}}$ :  $2 \mu\text{m}$
  - $g$ :  $0.15 \mu\text{m}$
- Agreement with Monte Carlo





# Preliminary Results (1)

## Multilayer y-Distance



RO Side

HV Side




Mean: 8.0 (3.7)  $\mu\text{m}$

RMS: 26.8 (13.8)  $\mu\text{m}$

Mean: 5.0 (1.5)  $\mu\text{m}$

RMS: 22.7 (10.8)  $\mu\text{m}$

N.B.: Blue circles mark repaired chambers, values given in parentheses are without these MDTs  
Error bars denote RMS spread of single tube deviation from linear fit to multilayer data





# Preliminary Results (2)

## Multilayer z-Displacement

RO Side

HV Side



Mean: 4.1 (9.8)  $\mu\text{m}$

RMS: 31.5 (9.9)  $\mu\text{m}$

Mean: -22.8 (-14.8)  $\mu\text{m}$

RMS: 23.9 (10.4)  $\mu\text{m}$

N.B.: Blue circles mark repaired chambers, values given in parentheses are without these MDTs  
 Error bars denote RMS spread of single tube deviation from linear fit to multilayer data



# SUMMARY

- LMU Cosmic Ray Facility operates in series test mode since September 2003



# SUMMARY

- LMU Cosmic Ray Facility operates in series test mode since September 2003
- Present rate: 1 chamber per week



# SUMMARY

- LMU Cosmic Ray Facility operates in series test mode since September 2003
- Present rate: 1 chamber per week
- Chamber commissioning (leak rate, electronics, response)



# SUMMARY

- LMU Cosmic Ray Facility operates in series test mode since September 2003
- Present rate: 1 chamber per week
- Chamber commissioning (leak rate, electronics, response)
- Chamber calibration achieves expected precision:
  - $\sigma(10 \mu\text{m})$  on wire positions
  - Few  $\mu\text{m}$  on chamber geometry

Valuable anchor points for the calibration with LHC data



# SUMMARY

- LMU Cosmic Ray Facility operates in series test mode since September 2003
  - Present rate: 1 chamber per week
  - Chamber commissioning (leak rate, electronics, response)
  - Chamber calibration achieves expected precision:
    - $\sigma(10 \mu\text{m})$  on wire positions
    - Few  $\mu\text{m}$  on chamber geometry
- Valuable anchor points for the calibration with LHC data
- 31 BOS/BOF MDT chambers analyzed so far
    - ATLAS leak rate limit fulfilled
    - Very good homogeneity of tube response
    - Consistent chamber geometry throughout production time





# Additional Slides



# Leak Rate Meas. (1)

- Max. allowed leak rate:  $2 \times N_{\text{Tubes}} \times 10^{-8}$  bar l/s  
→ 0.68 mbar / d
- 3460 O-ring seals in each chamber
- Leak test with He leak detector in sniffer mode, Ar/He mixture at 3 bar (2.6 bar Ar, 0.4 bar He)
- Precision absolute pressure measurement for each multilayer separately (0.1 mbar accuracy)
- $\delta T = 0.1 \text{ }^\circ\text{C} \rightarrow \delta p = 1 \text{ mbar}$   
⇒ need good temperature measurement / stabilization


**Difficult for a chamber of this size!**

[Back](#)





# Fit Functions



Leading edge

$$F(t) = p_0 + \frac{A_0}{1 + \exp\left(\frac{t_0 - t}{T_0}\right)}$$


Trailing edge

$$G(t) = p_m + \frac{\alpha_m \cdot t + A_m}{1 + \exp\left(\frac{t - t_m}{T_m}\right)}$$

Back





# Preliminary Results (3)



## Layer y-Distance

RO Side

HV Side



[Back](#)