

**20 April 1999
DRAFT**

Quality Assurance

for ATLAS MDT Chamber Construction

Task Owner QA/QC Procedures

Description of the Quality Assurance Procedures for the Construction of the Monitored Drift Tube chambers for the ATLAS muon spectrometer.

Table 1: Quality control tests of drift tube materials at the chamber production sites

Test	Acceptance criteria	Reaction if failed	Data base	Comment
Aluminium tube visual inspection of inside and outside	no obvious defects or holes; proper cleaning; defanning, scratchiness, bar code, packing	reject tube, notify supplier	central	1: sample test/batch 2: every tube before wiring
Outer diameter envelope, from 8 points on circumference	23370 – 15 μ m	reject box	central	sample test/batch
Wall thickness, at 8 points on circumference	120 – 30 μ m	reject box	central	sample test/batch
Length l	$l = 0.5$ mm ($l \leq 1$ m) $l = 0.7$ mm ($l > 1$ m)	reject box	central	sample test/batch
Scratchiness	insertion in β_4 without difficulties	reject tube, notify supplier	central	sample test/batch
Wire visual inspection	no defects of gold-plating; proper cleaning, no kinks	reject spool	central	1: first meters and every 100 m per spool under microscope; 2: inspection during wiring
Knurling visual inspection	proper cleaning and no obvious defects of plastic; O-rings, wire location; A1 reference surface, crimp tube	reject endstop, notify supplier	central	1: sample test/batch 2: each endstop before wiring
Outer diameter envelope, from 8 points on circumference (optional)	32020 – 10 μ m	reject batch	central	sample test/batch
Wire locator outer diameter	within tolerance	reject batch	central	sample test/batch

Table 2: Quality control tests of drift tubes at the chamber production sites

Test	Acceptance criteria	Reaction if failed	Data base	Comment
Drift tube visual inspection	no obvious damage of tube or endplug; no visible defects of tube and wire entry; tube correctly sealed	reject tube; adjust wiring station	local	each tube after wiring; before chamber assembly
Aluminum tube outer diameter envelope in endplug region	less than 30.320 mm	adjust wiring setup	local	sample test/day after wiring
Length l	$l = 0.5$ mm at $20 - 12^\circ\text{C}$	reject drift tube; adjust wiring station	local	1: sample test/day 2: each tube on chamber assembly jig
Relative azimuthal orientation of endplugs	± 10 mrad	reject drift tube; adjust wiring station	local	1: sample test/day 2: each tube on chamber assembly jig
Straightness	insertion in jig without difficulties	reject drift tube	local	1: sample test/day 2: each drift tube during chamber assembly
Ground contact resistance	less than 100 m Ω	repeat laser welding	local	1: sample test/day 2: monitoring of selected tubes over time

Table 3: Quality control tests for all drift tubes at the chamber production sites

Test	Acceptance criteria	Reaction if failed	Data base	Comment
Drift tube				
Room temperature	$20 \pm 2^\circ \text{C}$	adjust	local	during tube tests
Relative humidity (optional)			local	monitoring
Temperature of tube	$20 \pm 1^\circ \text{C}$	adjust temperature or tension	local	during tube assembly
Temperature of tube	known within $\pm 1^\circ \text{C}$	repeat measurement	central	during wire tension measurement
Wire tension (oscillation frequency)	within $\pm 5\%$ of the nominal value at $20 \pm 1^\circ \text{C}$	reject drift tube	central	1: shortly after tube wiring 2: after min. two months, before assembly
Wire location at the tube ends	within $\pm 25 \mu\text{m}$ of the center of the endplug ref. surface in w and z	reject drift tube; inspect endplugs and wiring station	central	sample test on day of wiring; tube held as in assembly (1); incl. test of coaxiality of endplugs; measurements at 0 and 1 SCP
Pressure test at 3 bar overpressure	no obvious leaks	reject drift tube; inspect endplugs; adjust wiring station	local	before leak test
Leak rate at 2 bar overpressure	less than 10^{-6} bar l/s	reject drift tube; inspect endplugs; adjust wiring station	central	
UV stability test: leakage current	less than 2 nA/m	reject drift tube; inspect endplugs; adjust wiring station	central	with Ar:CO ₂ (30:7) at 3 bar and 3100 V (1.3×10^4 gas gain)
UV stability test: cosmic count rate (optional)	within $\pm 3\%$ of nominal value	reject drift tube; inspect endplugs; adjust wiring station	central	with Ar:CO ₂ (30:7) at 3 bar and 3100 V (1.3×10^4 gas gain)

Table 4: Drift tube test equipment at the production sites

Site	Wire tension (noz. frequency)	Wire position	Leak rate (whole tube)	IV test (leakage current)	IV test (emamic rate)
Preiburg	Excitation in B-field	Brandeis X-ray system	Leak detector with single-tube containers	IV system with pA-meter	Yes
LNU/MPI (accept. test)	CAEN SY202 meter, excitation in B-field	Brandeis X-ray system, MPI 33	Pressure rise in evacuated volume at endcap (8 tubes sim.)	IV system with 1 nA sensitivity	BNI, preamp, shaper
NTU Athens	CAEN SY202 meter, excitation in B-field	Brandeis X-ray system	Leak detector, single-tube container	As Pavia (single-tube)	
Univ. Athens			as NTU Athens (after module 3)		
Thessaloniki (accept. test)	excitation in B-field			CAEN SY127 (10 channels), 1 nA sensitivity IV system	
Firenze	Electrostatic excitation, multi-channel system, integration with leak test	Electron spectre, as Pavia/Rome	Helium leak detector, 30 single-tube containers	CAEN SY30 (20 channel) 1 nA sensitivity IV system, integration with leak test	Yes
Cosenza	CAEN SY202 meter, excitation in B-field, integration with leak test	Electron spectre, as Pavia/Rome	As Pavia, automatic control system	CAEN SY30 (20 channel) 1 nA sensitivity IV system, integration with leak test	
Pavia	As Rome	Electron spectre (EMMI)	Argon mass spectrometer, 10 single-tube containers (commercial system)	IV system (10 channels) with pA-meter, integration with leak test	
Rome	Excitation in B-field, multi-channel	Electron spectre (EMMI)	As Frascati or Pavia,	As Pavia	
NIKHEF	Mechanical excitation, piezoelectric measurement	Electron spectre, as Pavia/Rome	Helium leak detector, multi-tube container	Multi-channel IV system, integration with leak test	Yes
Dubna (also for MPI)	Excitation in B-field, meter ensemble design	Brandeis X-ray system, MPI 33	Helium mass spectrometer, multi/single-tube containers	CAEN SY30 (20 channel) 1 nA sensitivity IV system	BNI, preamp, shaper
Protvino	Excitation in B-field, meter ensemble design	Brandeis X-ray system	Mass spectrometer		
Boston	Excitation in B-field, meter ensemble design	Brandeis X-ray system	Mass spectrometer, multi-tube container	Multi-channel IV system, integration with leak test	Yes
Michigan	As Seattle	Electron spectre, as Pavia/Rome	Helium leak test, evacuated volume at end-cap, and moving along tube	Multi-channel IV system	
Seattle	Excitation in B-field, meter ensemble design	Electron spectre, as Pavia/Rome	As Michigan	As Michigan	

Table 5: Quality control measurements during chamber assembly.

Test	Acceptance criteria	Reaction if failed	Data base	Comment
Environment				
Room temperature	20 – 15 C	adjust	local	before aligning
Relative humidity	50 – 10 %	adjust	local	before aligning
Atmospheric pressure (optional)			local	monitoring
Temperature of chamber	20 – 0.5° C	adjust	local	before aligning
Temperature of jigging	20 – 0.5° C	adjust	local	before aligning
Temperature difference between chamber and jig	< 0.2° C	adjust	local	before aligning
Spacer assembly				
Clear gaps between tube layer on vents and cross plates	200 – 1000 μ m	adjust	local	both orientations of cross plates around z-axis
O₂-chamber gas system				
Leak rate	less than 10 ⁻⁹ bar l/s	repair	local	of pre-assembled gas manifolds
Flow rate/tube	to be specified	repair		for pre-assembled gas manifolds

Table 6: Quality control measurements during chamber assembly (cont.)

Test	Acceptance criteria	Reaction if failed	Data base	Comment
Assembly of tube layers vacuum section underpressure	at nominal value	adjust	local	intra positioning on cards during gluing
Horizontal gaps between tubes	not more than two adjacent tube walls touching, no adjacent endspings touching	relocate drift tubes		before gluing
Vertical position of endsping reference surfaces	-10 μm of nominal value	relocate drift tubes	local	before gluing
Sphere locations	-10 μm of nominal value	adjust	local	before gluing, with sphere and in-plane mentions
Outer cross plate rods on the assembly table	-10 μm	adjust	local	before gluing, with temporary cross plate mentions
Middle cross plate rods on the assembly table	-20 μm	adjust	local	before gluing, with temporary cross plate mentions

Table 7: Quality control tests of assembled chambers at the production sites

Test	Acceptance criteria	Reaction if failed	Data base	Comment
Mechanical Tests				
Sag of chamber with kinematical supports before sag compensation		store data	central	w readings of in-plane members
Sag of chamber on kinematical supports after sag compensation	within -20μ of wire sag	adjust sag compensation until tolerance reached, store data	central	w readings of in-plane members
Deformation of cross plates on kinematical support (optional)	$< 20 \mu$ m	store data	central	with temporary cross plate sag members

Table 8: Quality control tests of assembled chambers at the production sites (cont.)

Test	Acceptance criteria	Reason if failed	Data base	Comment
Operation Tests				
Pressure test at 1 bar	test done; no obvious leaks	repair gas to unfold; repair/disconnect family inlets, stove II)	central	before leak test
Leak rate at 3 bar	less than 2×10^{-9} bar l/s per tube	repair gas to unfold; repair/disconnect family inlets, stove II)	central	
HV stability: leakage current	less than 5 nA/channel	replace electronics boards; identify; spotter/disconnect family drift inlets; stove II)	central	with installed electronics boards; with baseline gas at 3 bar and nominal and 5% nominal gas gain
HV stability: cosmic count rate (optional)	less than 5% nominal value	identify noisy channels; stove II)	central	with installed electronics boards; with baseline gas at 3 bar and nominal gas gain
Operation in cosmic ray test stand	evaluation of performance; noise level; efficiency; rate/turn rate; max. drift time; resolution vs. γ ; uniformity local wire displacements	make chamber operational; stove II) of family inlets	central	with test electronics; with baseline gas at 3 bar and nominal gas gain
Wire location measurement with cosmic rays (optional)	no systematic deviations from expected wire grid	store wire location data and chamber II); adjust assembly tooling in case of deviations	central	track reconstruction in cosmic ray tower

Table D: Quality control tests of assembled chambers during storage and at CERN

Test	Acceptance criteria	Reaction on failure	Data base	Comment
Visual inspection	no visible damage	perform possible repairs, mark chamber for X-ray tomograph and full leak test		acceptance test after transport to CERN
Leak rate at 3 bar	less than 2×10^{-9} bar l/s per unit	repair gas manifold, repair/disconnect faulty inlets, store II)	central	1: full leak test for one chamber per transport to CERN (acceptance test) or if visible damage of chamber 2: monitoring of pressure (at constant temperature) over storage time
Wire location measurement with X-ray tomograph (incl. location of wire on the algorm. platform)	± 20 μ m rms in x and z with respect to expected wire grid	store wire location data and chamber II), adjust assembly tooling in case of deviations, measure chambers since problem first detected	central	1: sample test/production site 2: for chambers with expected mechanical problems
HV stability; leakage current	less than 5 nA/channel	replace electronics boards, identify, disconnect faulty inlets, store II)	central	after mounting of final electronics, with baseline gas at 3 bar and nominal and 2 \times nominal gas gain
Operating test	evaluation of performance: pulse test (correct connections), signals from all channels, noise level, random rate, uniformity	replace electronics, make chamber operational	local	after mounting of final electronics, with baseline gas at 3 bar and nominal operating conditions
Wire tension (osc. frequency)	within $\pm 5\%$ of the nominal value at given temperature	store data, notify production sites, measure other chambers	central	for one chamber/production site at regular intervals over storage time (temperature fixes to -12° C)
Inlet ground contact resistance	less than 100 m Ω	store data, notify production sites, measure other chambers	central	for one chamber/production site at regular intervals over storage time