

28 April 1999
DRAFT

Quality Assurance

for ATLAS MDT Chamber Construction

Task Owner QA/QC Procedures

Description of the Quality Assurance Procedures for the Construction of the Monitored Drift Tube chambers for the ATLAS muon spectrometer.

Table 1: Quality control tests of drift tube materials at the chamber production sites

| Test | Acceptance criteria | Reaction if failed | Data base | Comment |
|--|---|-------------------------------------|-----------|---|
| Aluminium tube visual inspection of inside and outside | no obvious defects or holes, proper cleaning, deburring, straightness, bar code, packing | reject tube, notify supplier | central | 1: sample test/batch 2: every tube before wiring |
| Outer diameter envelope, from 8 points on circumference | 23370 – 15 μ m | reject box | central | sample test/batch |
| Wall thickness, at 8 points on circumference | 120 – 30 μ m | reject box | central | sample test/batch |
| Length l | $l = 3.5$ mm ($l \leq 1$ m) $l = 3.7$ mm ($l > 1$ m) | reject box | central | sample test/batch |
| Straightness | insertion in 54 without difficulties | reject tube, notify supplier | central | sample test/batch |
| Wire visual inspection | no defects of gold-plating, proper cleaning, no kinks | reject spool | central | 1: first meters and every 100 m per spool under microscope, 2: inspection during wiring |
| Knurling visual inspection | proper cleaning and no obvious defects of plastic, Coatings, wire locator, A1 reference surface, crimp tube | reject endspine, notify supplier | central | 1: sample test/batch 2: each endspine before wiring |
| Outer diameter envelope, from 8 points on circumference (optional) | 33020 – 10 μ m | reject batch | central | sample test/batch |
| Wire locator outer diameter | within tolerance | reject batch | central | sample test/batch |

Table 2: Quality control tests of drift tubes at the chamber production sites

| Test | Acceptance criteria | Reaction if failed | Data base | Comment |
|---|---|---|-----------|--|
| Drift tube visual inspection | no obvious damage of tube or endstop, no visible defects of tube and wire strips, tube correctly sealed | reject tube, adjust wiring station | local | each tube after wiring, before chamber assembly |
| Aluminum tube outer diameter envelope in endstop region | less than 30.020 mm | adjust wiring setup | local | sample test/day after wiring |
| Length l | $l = 0.5$ mm at $20 \pm 1^\circ$ C | reject drift tube, adjust wiring station | local | 1: sample test/day 2: each tube on chamber assembly jig |
| Relative axial orientation of endstops | ± 10 mrad | reject drift tube, adjust wiring station | local | 1: sample test/day 2: each tube on chamber assembly jig |
| Straightness | insertion in jig without difficulties | reject drift tube | local | 1: sample test/day 2: each drift tube during chamber assembly |
| Ground contact resistance | less than 100 m Ω | repeat laser welding | local | 1: sample test/day 2: monitoring of selected tubes over time |

Table 3: Quality control tests for all drift tubes at the charater production sites

| Test | Acceptance criteria | Reaction if failed | Data base | Comment |
|---|--|--|-----------|--|
| Drift tube | | | | |
| Room temperature | $20 \pm 2^\circ \text{C}$ | adjust | local | during tube tests |
| Relative humidity (optional) | | | local | monitoring |
| Temperature of tube | $20 \pm 1^\circ \text{C}$ | adjust temperature or tension | local | during tube assembly |
| Temperature of tube | known within $\pm 1^\circ \text{C}$ | repeat measurement | central | during wire tension measurement |
| Wire tension (oscillation frequency) | within $\pm 5\%$ of the nominal value at $20 \pm 1^\circ \text{C}$ | reject drift tube | central | 1: shortly after tube wiring 2: after min. two months, before assembly |
| Wire location at the tube ends | within $\pm 25 \mu\text{m}$ of the center of the endplug ref. surface in x and y | reject drift tube, inspect endplugs and wiring station | central | sample test on day of wiring, tube held as in assembly (1), incl. test of stability of endplugs, measurements at 0 and 15V |
| Gas pressure test at 3 bar overpressure | no obvious leaks | reject drift tube, inspect endplugs, adjust wiring station | local | |
| Gas leak rate at 2 bar overpressure | less than 10^{-9} bar l/s | reject drift tube, inspect endplugs, adjust wiring station | central | after pressure test |
| UV stability test: leakage current | less than 2 nA/m | reject drift tube, inspect endplugs, tube, wire | central | with Ar:CO ₂ (33:7) at 3 bar and 3100 V |
| UV stability test: cosmic count rate (optional) | within $\pm 3\%$ of nominal value | reject drift tube, inspect endplugs, tube, wire | central | with Ar:CO ₂ (33:7) at 3 bar and 3100 V |

Table 4: Drift tube test equipment at the production sites

| Site | Wire tension (max. frequency) | Wire position | Leak rate (whole tube) | IV test (leakage current) | IV test (cosmic rate) |
|-----------------------------|--|---------------------------------|--|---|--------------------------|
| Freiburg | Excitation in B-field | Brandeis N-ray system | Leak detector with single-tube containers | IV system with pA-meter | Yes |
| LNU/MPI (accept. test) | CAEN SV502 meter; excitation in B-field | Brandeis N-ray system, MPI 3g | Pressure rise in evacuated volume at sampling (8 tubes/str.) | IV system with 1 nA sensitivity | BNI, presamps, sharper |
| NTU Athens | CAEN SV502 meter; excitation in B-field | Brandeis N-ray system | Leak detector; single-tube container | As Pavia (single-tube) | |
| Univ. Athens | | | as NTU Athens (after module 3) | | |
| Thessaloniki (accept. test) | excitation in B-field | | | CAEN SV127 (10 channels); 1 nA sensitivity; IV system | |
| Firenze | Electrostatic excitation; multi-channel system; integration with leak test | Electronoagnette; as Pavia/Roma | Helium leak detector; 30 single-tube containers | CAEN SV503 (26 channel) 1 nA sensitivity; IV system; integration with leak test | Yes |
| Cosenza | CAEN SV502 meter; excitation in B-field; integration with leak test | Electronoagnette; as Pavia/Roma | As Pavia; automatic control system | CAEN SV503 (26 channel) 1 nA sensitivity; IV system; integration with leak test | |
| Pavia | As Rome | Electronoagnette (CEM4) | Argon mass spectrometer; 10 single-tube containers (commercial system) | IV system (10 channels) with pA-meter; integration with leak test | |
| Rome | Excitation in B-field; multi-channel | Electronoagnette (CEM4) | As Frascati or Pavia; | As Pavia | |
| NIKHEF | Mechanical excitation; piezoelectric measurement | Electronoagnette; as Pavia/Roma | Helium leak detector; multi-tube container | Multi-channel IV system; integration with leak test | Yes |
| Dubna (also for MPI) | Excitation in B-field; meter custom design | Brandeis N-ray system, MPI 3g | Helium mass spectrometer; multi/single-tube containers | CAEN SV503 (26 channel) 1 nA sensitivity; IV system | BNI, presamps, sharper |
| Provincino | Excitation in B-field; meter custom design | Brandeis N-ray system | Mass spectrometer | | |
| Boston | Excitation in B-field; meter custom design | Brandeis N-ray system | Mass spectrometer; multi-tube container | Multi-channel IV system; integration with leak test | Yes |
| Michigan | As Seattle | Electronoagnette; as Pavia/Roma | Helium leak tester; evacuated volume at end-plug and moving along tube | Multi-channel IV system | |
| Seattle | Excitation in B-field; meter custom design | Electronoagnette; as Pavia/Roma | As Michigan | As Michigan | |

Table 5: Quality control tests during chamber assembly.

| Test | Acceptance criteria | Reaction if failed | Data base | Comment |
|--|------------------------------------|--------------------|-----------|---|
| Environment | | | | |
| Vacuum temperature | 20 – 15°C | adjust | local | before gluing |
| Relative humidity | 70 – 10 % | adjust | local | before gluing |
| Atmospheric pressure (optional) | | | local | monitoring |
| Temperature of chamber | 20 – 0.5°C | adjust | local | uniform, before gluing |
| Temperature of jigging | 20 – 0.5°C | adjust | local | uniform, before gluing |
| Temperature difference chamber-jigging | < 0.2°C | adjust | local | during gluing |
| Spacer assembly | | | | |
| Clear gaps between tube layer on ends and cross plates | 200 – 1000 µm | adjust | local | both orientations of cross plates around 2-axis |
| On-chamber gas system | | | | |
| Leak rate | less than 10 ⁻⁹ bar l/s | repair | local | of pre-assembled gas manifolds |
| Flow rate/tube | to be specified | repair | | for pre-assembled gas manifolds |

Table 6: Quality control tests during chamber assembly (cont.)

| Test | Acceptance criteria | Reaction if failed | Data base | Comment |
|---|---|-----------------------|-----------|--|
| Assembly of tube layers: vacuum suction underpressure | at nominal value | adjust | local | tube positioning on combs during gluing |
| Horizontal gaps between inlets | not more than two adjacent tube walls touching, no adjacent endflaps touching | relocate drift inlets | local | before gluing |
| Height of endflap reference surfaces | within $\pm 10 \mu\text{m}$ of nominal value in α | relocate drift inlets | local | before gluing |
| Stability of in-plane non-linear readings (in case displacement) Sphere locations | within $\pm 10 \mu\text{m}$ of nominal value in α and β | adjust | central | after each gluing step (definition of zero of in-plane nonlinears), after correction for middle |
| Outer cross plate sag on the assembly table (optional) | within $\pm 10 \mu\text{m}$ of nominal value in α and β | adjust | local | before each gluing step, with sphere and in-plane nonlinears |
| Middle cross plate sag on the assembly table (optional) | zero within $\pm 10 \mu\text{m}$ | adjust | local | before gluing of a layer, measured with temporary cross plate sag nonlinears |
| | zero within $\pm 20 \mu\text{m}$ | adjust | local | before gluing of a layer, measured with in-plane nonlinears plus outer cross plate sag correction |
| Alignment Platforms: Angular alignment of axial/proxial platforms | within $\pm 80 \mu\text{rad}$, $\pm 200 \mu\text{rad}$, $\pm 80 \mu\text{rad}$ around β_1 , α_1 , β_2 -axes with chamber coord. axes, orthog. $\pm 100 \mu\text{rad}$ cross plate length | store data | central | after each gluing step (initially); includes accuracy of rec. of thermal and gravitational deformations with in-plane system |
| Angular alignment of projective platforms | within $\pm 200 \mu\text{rad}$, $\pm 80 \mu\text{rad}$, $\pm 80 \mu\text{rad}$ around β_1 , α_1 , β_2 -axes with chamber coordinate axes | store data | central | includes accuracy of rec. of thermal and gravitational deformations with in-plane system |

Table 7: Quality control tests of all assembled chambers at the production sites

| Test | Acceptance criteria | Reaction if failed | Data base | Comment |
|---|------------------------------|---|-----------|---|
| Mechanical Tests | | | | |
| Sag of chamber with kinematical supports before sag compensation | | store data | central | σ readings of in-plane monitors |
| Sag of chamber on kinematical supports after sag compensation | within -20μ of wire sag | adjust sag compensation until tolerance reached, store data | central | σ readings of in-plane monitors |
| Deformation of cross plates on kinematical support. (recommended for IEM, IRO) | $< 20 \mu\text{m}$ | store data | central | with temporary cross plate sag monitors and FEA model |

Table 8: Quality control tests of all assembled chambers at the production sites (cont.)

| Test | Acceptance criteria | Reaction if failed | Data base | Comment |
|--|--|---|-----------|---|
| Operation Tests | | | | |
| Gas pressure test at 3 bar overpressure | test done; no obvious leaks | repair gas manifold; repair/disconnect family inlets; store II) | central | |
| Gas leak rate at 2 bar overpressure | less than 2×10^{-9} bar l/s per inlet | repair gas manifold; repair/disconnect family inlets; store II) | central | after pressure test |
| HV stability; leakage current | less than 2 nA/ro \rightarrow 5 nA per channel | replace electronics boards; identify; sparger/disconnect family drift inlets; store II) | central | with installed electronics boards; baseline gas at 3 bar and nominal and so nominal gas gain |
| HV stability; cosmic count rate (optional) | within $\pm 3\%$ of nominal value | identify noisy channels; store II) | local | with installed electronics boards; baseline gas at 3 bar and nominal gas gain |
| Operation in cosmic ray test stand | evaluation of performance; noise level; efficiency; random rate; max. drift time; resolution vs. γ ; uniformity; local wire displacement; stable performance of all channels over 1-2 weeks | make chamber operational; store II) of family inlets | local | with test electronics; baseline gas at 3 bar and nominal gas gain |
| Wire location measurement with cosmic rays (optional) | no systematic deviations from expected wire grid | store wire location data incl. meas. errors; adjust assembly tooling in case of deviations | central | track reconstruction in cosmic ray lower |

Table D: Quality control tests of all assembled chambers after transport to CERN and during storage

| Test | Acceptance criteria | Reaction on failure | Data base | Comment |
|-------------------------------|---|---|-----------|---|
| Visual inspection | no visible damage | perform possible repairs, mark chamber for X-ray tomograph and full leak test | | acceptance test after transport to CERN |
| Gas leak rate at 3 bar | less than 2×10^{-9} bar l/s per tube | repair gas manifold, repair/disconnect faulty tubes, store II) | central | 1: full leak test for one chamber per transport to CERN (acceptance test) or if visible damage of chamber 2: monitoring of pressure (at known temperature) over storage time |
| HV stability; leakage current | less than 5 nA/channel | replace electronics boards; identify, disconnect faulty tubes; store II) | central | after mounting of final electronics, with baseline gas at 3 bar and nominal and $2 \times$ nominal gas gain |
| Operating test | evaluation of performance: pulser test (correct connections); signals from all channels; noise level; random rate; uniformity | replace electronics; make chamber operational | local | after mounting of final electronics, with baseline gas at 3 bar and nominal operating conditions |

Table 10: Quality control tests of selected charaters from each production site after transport to CERN and during storage

| Test | Acceptance criteria | Reaction on failure | Data base | Comment |
|--|---|---|-----------|--|
| Wire location measurement with X-ray tomograph (incl. location of wire on the shunt, platform) | $-20 \mu\text{m}$ rms in x and y with respect to the expected wire grid | store wire location data and charater ID; adjust assembly tooling in case of deviations; measure charaters since problem first detected | central | 1: sample test/production site 2: for charaters with expected mechanical problems |
| Wire tension (osc. frequency) | within $\pm 5\%$ of the nominal value at given temperature | store data; notify production sites; measure other charaters | central | for one chamber/production site at regular intervals over storage time (temperature meas. to $\pm 1^\circ\text{C}$) |
| Inlet ground contact resistance | less than $100 \text{ m}\Omega$ | store data; notify production sites; measure other charaters | central | for one chamber/production site at regular intervals over storage time |